



Drilling Capacity: 1,200' Portable Trailer Mounted Drill Rig

Drawworks: Walker-neer Double Drum Drawworks

Main Power: Cat 3406, 425 Bhp @ 2100 Rpm

Mast: Fixed 60 Foot Single, Rated 120,000#

Rotary Table: Ideco 145 – 14.5 Inch

Compressor: Sullair 900 Cfm @ 200 Psi With Mack Engine Leroi 450 Cfm @ 200 Psi With D-353 Cat Diesel Engine

Mud Pump: 2-mission Magnum, 8×6 With 8v91 Detroit Diesel 550 Hp Engine

Generator: 50 Kw Generator

Welders: Miller 250 Dialarc Inverter Walker 1units + Wire Feed Units

Swivel: Gumbo Buster, 8 Inch Discharge

Kelly Drum Block: 50 Ton Brewster, 3-sheave, 1-1/8" Wire Rope

Main Drum Block: 75 Ton Brewster, 3-sheave, 1-1/8" Wire Rope

Fuel Tank: 1,000 Gallon

Kelly: 7" Od X 4" Id Square X 42 Feet

Drill Pipe: 1,200', 6-5/8" If, 31' Random, 27.70#/ft

Drill Collars: 3 – 11" Od X 5" Id X 31', 245#/ft

Dog House: Self Contained Unit With Crew Lockers, Work Room With Tool Storage, Mast Lighting, Double Shot Deviation Tool With Texas First Industrial Wireline Winch

